## Large slab ceiling box





## Large slab ceiling box 105

- · for in-factory installation
- · Fastening to the formwork by means of KAISER adhesive foil (Art. No. 1219-00) or hot glue
- Installation height 105 mm, with metal nut M5 for light hook (min. hook length: 105 mm + plaster thickness)
- · for space frame heights up to 11 cm (incl. distance pieces)
- · With closing cover for on-site fitting of conduits
- · maximum light hook load according to DIN EN 60670 100 N (10 kg)

Article no:	1227-54
EAN:	4013456252332
Exit opening Ø	60 mm
Depth	105 mm
Markings for cables and DIN EN conduits up to Ø 25 mm	8
Markings for cables and DIN EN conduits up to $\varnothing$ 32 mm	-
Number of parts	2
especially suitable for hot glue attachment	Yes
Dispatch	100

The large slab ceiling box is suitable for in-factory installation in prefabricated ceilings. The version with a slot for the system magnet (Art. No. 1299-69) or system magnet PLUS (Art. No. 1299-70) is ideally suited for quick attachment to system magnets that have already been set automatically. The large slab ceiling boxes are already a part of the ceiling when they reach the construction site and enable the quick insertion of empty conduits. The resealable quick-release cover can be opened with a quarter turn and so enables the quick and exact creation of conduit entries using punch pliers (Art. No. 1286-33/-34).

- · For in-factory installation
- · Slot for system magnet (Art.-No. 1299-69) and system magnet PLUS (Art.-No. 1299-70)
- · Large adhesive area with rough surface structure for a secure fit on the formwork table
- · 115-mm installation height guarantees optimal transport conditions for prefabricated ceilings
- · Quick-release cover for fast cutting of conduit entries using punch pliers
- · Integrated M5 domed cap nut ensures secure fitting of a light hook.
- · With closing cover for on-site fitting of conduits

**INNOVATION** 

